
Volume 12 Number 29 7 August 2021 Pages 9855-10118

Chemical Science



ISSN 2041-6539



EDGE ARTICLE

Yasutaka Kuwahara, Hiromi Yamashita *et al.*A quasi-stable molybdenum sub-oxide with abundant oxygen vacancies that promotes CO₂ hydrogenation to methanol

Chemical Science



EDGE ARTICLE

View Article Online



Cite this: Chem. Sci., 2021, 12, 9902

d All publication charges for this article have been paid for by the Royal Society of Chemistry

abundant oxygen vacancies that promotes CO₂ hydrogenation to methanol† Yasutaka Kuwahara, 🔟 *^{abcd} Takashi Mihogi, ^a Koji Hamahara, ^a Kazuki Kusu, ^a

Hisayoshi Kobayashi^{ae} and Hiromi Yamashita ** **abc

A quasi-stable molybdenum sub-oxide with

Production of methanol from anthropogenic carbon dioxide (CO₂) is a promising chemical process that can alleviate both the environmental burden and the dependence on fossil fuels. In catalytic CO₂ hydrogenation to methanol, reduction of CO_2 to intermediate species is generally considered to be a crucial step. It is of great significance to design and develop advanced heterogeneous catalysts and to engineer the surface structures to promote CO2-to-methanol conversion. We herein report an oxygen-defective molybdenum sub-oxide coupled with Pt nanoparticles (Pt/H_xMoO_{3-y}) which affords high methanol yield with a methanol formation rate of 1.53 mmol g_{-cat}^{-1} h⁻¹ in liquid-phase CO₂ hydrogenation under relatively mild reaction conditions (total 4.0 MPa, 200 °C), outperforming other oxide-supported Pt catalysts in terms of both the yield and selectivity for methanol. Experiments and comprehensive analyses including in situ X-ray absorption fine structure (XAFS), in situ diffuse reflectance infrared Fourier transform (DRIFT) spectroscopy and density functional theory (DFT) calculations reveal that both abundant surface oxygen vacancies (V_O) and the redox ability of Mo species in quasi-stable H_xMoO_{3-v} confer the catalyst with enhanced adsorption and activation capability to subsequently transform CO2 to methanol. Moreover, the Pt NPs act as H2 dissociation sites to regenerate oxygen vacancies and as hydrogenation sites for the CO intermediate to finally afford methanol. Based on the experimental and computational studies, an oxygen-vacancy-mediated "reverse Mars-van Krevelen (M-vK)" mechanism is proposed. This study affords a new strategy for the design and development of an efficient heterogeneous catalyst for CO₂ conversion.

Received 9th May 2021 Accepted 26th June 2021

DOI: 10.1039/d1sc02550c

rsc.li/chemical-science

Introduction

The continuous accumulation of anthropogenic CO₂ in the atmosphere aggravates global warming. The control and reduction of CO₂ emissions have been a worldwide challenge and pressing issue. Carbon capture and storage (CCS) has been deemed as a promising technology to drastically reduce CO₂ emissions; however, appropriate carbon capture and utilization (CCU) technology must be developed to further reduce CO₂ emissions in a sustainable manner. Catalytic conversion of

CO2 is capable of being transformed to several important C1 chemicals such as CO, formic acid, methanol, and methane via hydrogenation.⁵⁻⁹ Among those, methanol (CH₃OH) has attracted huge interest from industries and scientific community, because it can be used as a raw material for the production of formalin, acetic acid, olefins, and gasoline, and can be utilized as a fuel molecule for automobiles and fuel cells. 10,11 Methanol is currently produced from syngas (CO and H2), generated by a steam reforming process using methane contained in liquefied natural gas (LNG) and petroleum gas (LPG), under extreme operational conditions (T = 240-260 °C, P = 5-10 MPa), in which Cu-based catalysts (e.g. Cu/ZnO/Al2O3) are used as a traditional catalyst. 5,6,12,13 Production of methanol from anthropogenic CO2 existing in the atmosphere or being discharged from large stationary sources via hydrogenation using CO₂-free H₂ produced by renewable energy sources would be a green chemical process that could alleviate both the environmental burden and the dependence on fossil fuels. 14,15

anthropogenic CO2 into valuable chemicals is regarded as a sustainable and appealing approach to alleviate simultaneously the environmental crisis and energy demands.1-4

^aDivision of Materials and Manufacturing Science, Graduate School of Engineering, Osaka University, 2-1 Yamada-oka, Suita, Osaka 565-0871, Japan. E-mail: kuwahara@mat.eng.osaka-u.ac.jp; yamashita@mat.eng.osaka-u.ac.jp

^bInnovative Catalysis Science Division, Institute for Open and Transdisciplinary Research Initiatives (OTRI), Osaka University, 2-1 Yamada-oka, Suita, Osaka 565-

^{&#}x27;Unit of Elements Strategy Initiative for Catalysts & Batteries (ESICB), Kyoto University, Katsura, Kyoto 615-8520, Japan

^dJST, PRESTO, 4-1-8 Honcho, Kawaguchi, Saitama 332-0012, Japan

eKyoto Institute of Technology, Matsugasaki, Sakyo-ku, Kyoto 606-8585, Japan

[†] Electronic supplementary information (ESI) available. See DOI: 10.1039/d1sc02550c

Direct methanol synthesis from CO2/H2 via gas phase hydrogenation has been implemented industrially using supported Cu catalysts; however, a low equilibrium conversion of CO2 at the operational conditions is seen as a bottleneck limiting large-scale operations. Methanol synthesis from CO₂/ $H_2 (CO_2 + 3H_2 = CH_3OH + H_2O; \Delta H_{298}^0 = -49.5 \text{ kJ mol}^{-1}) \text{ is an}$ exothermic reaction, therefore, use of lower temperature and higher pressure conditions are thermodynamically more favorable.5,16 Recently, direct methanol synthesis in the liquid phase at lower temperatures has been studied, primarily because of easy control of the reaction temperature and easy extraction of products from the reaction system, which shifts the reaction equilibrium to the methanol production side. 17,18 Although Ru-based homogeneous catalysts are known to function as active catalysts under relatively mild conditions, addition of additive reagents to achieve high reaction rates and problems associated with product separation and catalyst recovery are critical drawbacks. 19-22 Alternatively, noble metal nanoparticle (NP) catalysts, such as Pt,23-27 Rh,28,29 and Re30 etc. have been studied as heterogeneous catalysts for this reaction. In particular, Pt NPs are indispensable for the promotion of CO₂ hydrogenation due to the efficient donation of their d-orbital electrons into the π^* antibonding system of CO_2 . It has been reported that the activity of Pt NP catalysts is enhanced by manipulating the particle shape and the compositions (e.g. alloying with Co)23,24 or by the coupling with proper support material (e.g. MoS₂),²⁵ leading to a high methanol yield even at

a low temperature of 150 °C. In catalytic CO₂ hydrogenation, activation and cleavage of the stable C=O bond of CO₂ to form intermediate species is generally considered to be the crucial step. Previous literatures have reported the importance of an oxygen vacancy (Vo) of metal oxides in the activation of CO₂. 31,32 For example, Bobadilla et al. spectroscopically understood that the oxygen vacancies of TiO2 support of Au/TiO2 catalyst participate in reverse water-gas shift (RWGS) reaction by activating CO2.33 Bhethanabotla and Kuhn et al. demonstrated that oxygen vacancy in La_{0.75}Sr_{0.25}FeO₃ perovskite-type oxide efficiently promotes CO2 conversion in RWGS reaction.34 Ge et al. demonstrated that the oxygen vacancy on the In₂O₃ surface assists CO₂ activation and hydrogenation and also stabilizes the key intermediates in CO2 hydrogenation to methanol by using DFT calculation.35 Previous studies demonstrated that oxygen vacancies formed in nonstoichiometric WO_{3-x} and MoO_{3-x} enable the light-assisted extraction of O atoms from CO₂ to form methane and CO, respectively.^{36,37} Thus, the assistance of oxygen vacancies in metal oxide is deemed as an appealing approach to activate molecular CO2 and weaken the C=O double bond. However, because V_O sites are replenished by the dissociated O atoms during the reaction, the catalytic cycle cannot be realized. Coupling of Vo sites and metal particles that simultaneously activate H₂ to regenerate V_O sites is the key to sustaining a continuous catalytic cycle, which has been demonstrated extensively over oxide-supported metal catalysts. 33,38-40 In this regard, our group reported that oxygen-defective molybdenum sub-oxide coupled with Pt NPs (Pt/H_xMoO_{3-v}) can function as a reusable catalyst for hydrodeoxygenation of sulfoxide to produce sulfide under mild reaction conditions, in which

abundant oxygen vacancies in H_xMoO_{3-y} act as the deoxygenation site and Pt NPs act as H_2 dissociation sites to continuously supply active H atoms for regenerating the oxygen vacancies.⁴¹ It is hypothesized that such a bifunctional catalytic system would be a viable catalyst for realizing simultaneous activation of CO_2 and H_2 and efficient hydrogenation of CO_2 to produce methanol.

In the present work, we report that an oxygen-defective molybdenum sub-oxide coupled with Pt NPs (Pt/H_rMoO_{3-v}) exhibits high methanol yield with a methanol formation rate of 1.53 mmol $g_{-cat}^{-1} h^{-1}$ in liquid-phase CO_2 hydrogenation under relatively mild reaction conditions (total 4.0 MPa, 200 °C). In situ XAFS, in situ DRIFT spectroscopy and DFT calculations were employed to investigate the reaction mechanism. The experiments and comprehensive analyses revealed that abundant surface oxygen vacancies and the redox ability of Mo species in quasi-stable H_xMoO_{3-v} endowed this catalyst with enhanced adsorption and activation capability to subsequently transform CO₂ to form the CO intermediate, and Pt NPs were found to act as H2 dissociation sites to regenerate oxygen vacancies and as hydrogenation sites of CO intermediate to finally afford methanol. This study provides new insights into the design and development of high-performance heterogeneous catalysts for CO2 hydrogenation reactions to produce methanol, which is a key chemical process for realizing CO2 reduction and sustainable methanol production.

Experimental

Synthesis of oxide-supported Pt catalysts

The Pt catalyst supported on α-MoO₃ (Pt/MoO₃) was prepared by a precipitation method using urea as a precipitant. 41 α-MoO₃ (1.0 g) was dispersed in 100 mL of distilled water containing 4.5 mL of K₂PtCl₄ solution (35 mM). To this suspension, 0.2 g of urea as a precipitation reagent was added, followed by vigorous stirring for 6 h at 95 °C to precipitate Pt2+ ions. The obtained slurry was centrifuged, washed with deionized water, and then dried at 100 °C in air overnight to give Pt/MoO3 (unreduced sample). The catalyst used in the hydrogenation process was prepared by reduction of Pt/MoO3 in a glass tube under a flow of H_2 (20 mL min⁻¹) for 30 min with a heating rate of 5 °C min⁻¹ to give $Pt/H_xMoO_{3-\nu}(T)$ (T represents the reduction temperature (°C)). The Pt loading was determined to be 1.3 wt% by inductively coupled plasma (ICP) analysis. The Pt/H_xMoO_{3- ν}(T) catalysts with various Pt contents were prepared in the same manner using different amounts of K₂PtCl₄ solution.

Other oxide-supported Pt catalysts were prepared in the same manner described above except for using different oxides as supports. Pd, Re, Ru and Cu catalysts supported on MoO₃ were also prepared in the same manner described above except for using Na₂PdCl₄, NH₄ReO₄, RuCl₃·*n*H₂O, and Cu(NO₃)₂··3H₂O as the precursors, respectively, instead of K₂PtCl₄.

Characterization

High-resolution transmission electron microscopy (HR-TEM) images were recorded on a JEOL ARM200F instrument operated at 200 kV accelerating voltage. The sample was dispersed in

ethanol by sonication, and the dispersion was dropped onto a Cu grid covered with carbon film in an Ar atmosphere to avoid sample oxidation. Power X-ray diffraction (XRD) patterns were obtained with a Rigaku Ultima IV diffractometer with Cu K_{α} radiation ($\lambda=1.54056~\mbox{Å}$) operated at 40 kV and 40 mA. X-ray photoelectron spectroscopy (XPS) measurements were performed on a Shimadzu ESCA-3400 photoelectron spectrometer using Mg K_{α} radiation (1253.6 eV) X-ray source at $<10^{-5}$ Pa. Samples were introduced to the XPS analysis chamber without exposure to the air to avoid sample oxidation. All binding energies were calibrated with the adventitious carbon (C 1s) peak at 284.5 eV.

Mo K-edge and Pt L3-edge XAFS spectra were recorded at the BL01B1 beamline at the SPring-8 facility, Japan Synchrotron Radiation Research Institute (JASRI), Harima, Japan. Si(311) and Si(111) double-crystal monochromators were used for the Mo K-edge and Pt L3-edge XAFS measurements, respectively. For pseudo in situ XAFS measurement, the samples, pretreated in a flow of H2, were sealed in a polyethylene bags without exposure to the air, and subjected to the XAFS measurement at room temperature. For in situ Mo K-edge XAFS measurement, a pelletized unreduced Pt/MoO₃ sample (φ 7 mm) was placed in a tailor-made quartz cell (Makuhari Rikagaku Garasu Inc.) equipped with a water-cooling condenser and an electric heater, which was connected to a gas-exchange system. After purging the cell with He, the sample was first reduced at 300 °C under a flow of 20% H_2/He (100 mL min⁻¹), kept at 200 °C, and then exposed to 20% CO₂/He (100 mL min⁻¹) and 20% H₂/He (100 mL min⁻¹) in turn. During these processes, Mo K-edge XAFS spectra were recorded in transmission mode to track the changes of Mo species. The obtained XAFS spectra were normalized by fitting the background absorption coefficient. After a k^3 -weighting, the extended XAFS (EXAFS) spectra were Fourier-transformed from the k space to the r space across the krange 3.0 < $k \, (\mathring{A}^{-1})$ < 11.0 to obtain the radial distribution functions (RDFs).

Temperature programmed reduction with hydrogen (H_2 -TPR) was carried out using a BELCATII system (Microtrac-BEL Corp.) equipped with a thermal conductivity (TCD) detector. A sample (ca. 50 mg) mounted in a quartz vessel was pretreated in a flow of Ar (30 mL min⁻¹) at 150 °C for 60 min to remove the physisorbed water, and then cooled to 50 °C. TPR profiles were collected by heating the samples from 50 to 500 °C with a heating rate of 10 °C min⁻¹ under a flow of 5% H_2 /Ar (50 mL min⁻¹). The effluent gas was passed through a trap containing a molecular sieve MS-4A to remove the produced water to determine the amount of H_2 consumed.

Thermogravimetric measurement (TG) was conducted in a flow of either air or $\rm N_2$ to determine the amounts of hydrogen and oxygen vacancies introduced in molybdenum sub-oxide samples, respectively. The weight change curves were obtained on a Rigaku Thermo plus EVO II. Unreduced sample placed in an alumina pan was first reduced in a flow of $\rm H_2$ (100 mL min $^{-1}$) at designated temperatures (100–400 °C) for 30 min, and then cooled to 50 °C. After switching the flow gas to either air or $\rm N_2$ (100 mL min $^{-1}$), the temperature was increased from 50 to 450 °C at a heating rate of 10 °C min $^{-1}$. Based on the

weight changes observed under the two different conditions, the stoichiometric compositions of the samples were determined.

In situ DRIFT measurement

DRIFT spectra were measured using a Shimadzu IRSpirit spectrometer, equipped with a triglycine sulfate (TGS) detector at a resolution of 4 cm⁻¹. For *in situ* DRIFT measurement, unreduced sample was placed in an alumina pan, introduced into a stainless-steel heat chamber (S.T. Japan Inc.) equipped with a water-cooling system and connected to gas cylinders, and prereduced at 300 °C in a flow of H₂ (20 mL min⁻¹) for 30 min. After prereduction, the cell was kept at 250 °C and a background spectrum was obtained. Subsequently, 1.0 MPa of CO₂ and 1.0 MPa of H₂ were successively introduced into the *in situ* cell, and the DRIFT spectra were recorded every 30 min. Each DRIFT spectrum was obtained by subtracting the background spectrum from each measured spectrum.

General procedure for CO2 hydrogenation

In a typical procedure, the as-prepared catalyst (ca. 50 mg) was placed in a glass tube, followed by reduction at 300 °C for 30 min in a flow of H_2 (20 min min⁻¹). The glass tube containing the prereduced catalyst (ca. 50 mg) and 1,4-dioxane (15 mL) were placed in a stainless-steel autoclave reactor (volume = 41 mL), purged three times with pure CO₂, and pressurized to 1.0 MPa with CO_2 and then to 4.0 MPa with H_2 (CO_2 : H_2 = 1:3). The reactor was heated to 200 °C and magnetically stirred (600 rpm) for 20 h. After the reaction, the reaction mixture was cooled to room temperature and depressurized, and the gas products were analyzed using a gas chromatograph (GC; Shimadzu GC-8A) with a 4 m active carbon column equipped with an FID detector and a methanizer (Shimadzu MTN-1). The liquid products were analyzed using GC-FID (column: Zebron ZB-FFAP, 50 m \times 0.32 mm) using 1-butanol as an external standard. The TON values were determined by dividing the quantity of CO2 converted by the number of moles of the total quantity of Pt contained in the catalyst. To examine the catalyst reusability, the catalyst was retrieved from the reaction solution by centrifugation (10 000 rpm, 5 min), washed with the solvent, and then subjected to next catalytic run.

DFT calculations

All DFT calculations were performed using the CASTEP program in Materials Studio 17.2. The Perdew–Burke–Ernzerhof exchange-correlation function within the generalized gradient approximation (GGA-PBE) with the ultrasoft core potential was employed for geometry optimization, and the double numerical plus d-function (DND) was chosen as the basis set. The electron configurations of the atoms were H: 1s¹, C: $2s^22p^2$, O: $2s^22p^4$, Mo: $4s^24p^64d^55s^1$, Pt: $5d^96s^1$, the plane wave cutoff energy was set to 300 to 340 eV. Considering the layered structure of $H_{0.9}MoO_3$ in Pt/ H_xMoO_{3-y} , a super cell slab model composed of $H_{32}Mo_{32}O_{96}$ including one Mo octahedra bilayer was constructed. The lattice parameters for the super cell are b=15.1776 Å, c=15.4438 Å, $\alpha=\gamma=90^\circ$, $\beta=93.727^\circ$. The a-axis

was taken as the direction of surface normal, and a was set to 30 Å including the vacuum region. For the slab model with a Pt NP, a Pt₂₀ cluster was loaded on the H_{0.9}MoO₃ (100) surface to model Pt/H_xMoO_{3-y} catalyst. ^{42,43} The bottom MoO₆ layer was fixed at the corresponding bulk position, while the top MoO₆ layer, the Pt₂₀ cluster and the molecules in the gas phase were allowed to relax during geometry optimizations. The adsorption energy ($E_{\rm ads}$) was defined as $E_{\rm ads} = E_{\rm total} - (E_{\rm sub} + E_{\rm molecule})$, where $E_{\rm total}$, $E_{\rm sub}$, and $E_{\rm molecule}$ are the total energies of the substrate optimized together with the adsorbate, the free substrate, and the free adsorbate molecule. The activation energy for transition state (TS) was defined as the difference energy between the TS and the local minimum just before the

Results and discussion

Liquid-phase CO_2 hydrogenation over oxide-supported Pt catalysts

In a preliminary study, liquid-phase CO_2 hydrogenation was carried out using Pt NPs catalysts immobilized on various oxide supports (Pt content: ca. 3 wt%) to search for a catalyst that provides a high methanol yield. The CO_2 hydrogenation reaction was performed using a stainless autoclave reactor (volume = 41 mL) filled with 4.0 MPa of CO_2/H_2 gas ($CO_2: H_2 = 1: 3$) at 200 °C for 20 h using catalyst (50 mg) pretreated with H_2 at 300 °C for 30 min (Table 1 and Fig. 1a). The main products observed in this reaction were CO_2 methanol, and methane. High CO_2 conversion rates were attained when easily reducible oxides such as MOO_3 , V_2O_5 , Nb_2O_5 and WO_3 were used as supports; Pt/H_xMoO_{3-y} catalyst provided the highest CO_2




Fig. 1 (a) Comparison of catalytic performance of various oxide-supported Pt catalysts in the liquid-phase CO₂ hydrogenation reaction (catalysts were all reduced at 300 °C for 30 min in a flow of H₂). (b) Time course of the product selectivity and CO₂ conversion over Pt/ H_xMoO_{3-y}(300) catalyst. (c) Effect of Pt loading on catalytic performance for Pt/H_xMoO_{3-y} catalyst (catalysts were all reduced at 200 °C for 30 min in a flow of H₂). (d) Effect of reduction temperature on catalytic performance for Pt/H_xMoO_{3-y}(T) catalyst and the stoichiometry of intercalated H atoms (x) and oxygen vacancies (y) in molybdenum sub-oxide (H_xMoO_{3-y}). Reaction conditions: catalyst (50 mg), 1,4-dioxane (15 mL), $P_{\text{CO}_2} = 1.0$ MPa, $P_{\text{H}_2} = 3.0$ MPa, 200 °C, 20 h.

conversion (25.0%) with the highest methanol selectivity ($Sel_{MeOH} = 33\%$) among the catalysts examined, which corresponded to a 1.53 mmol yield of methanol after 20 h of reaction (methanol production rate = 1.53 mmol $g_{-cat}^{-1} h^{-1}$) (entry 1), while Pt/V_2O_5 , Pt/Nb_2O_5 and Pt/WO_3 catalysts gave CO as the main product and methanol was hardly produced ($Sel_{MeOH} = 5$ –

Table 1 Liquid-phase CO₂ hydrogenation using various oxide-supported Pt catalysts^a

				Selectivity [%]				
Entry	Catalyst	Metal loading ^b [wt%]	CO ₂ conv. [%]	МеОН	CO	CH_4	Total TON ^c	TON for MeOH ^c
1	Pt/H_xMoO_{3-y}	1.3	25.0	33	55	12	1379	462
2	Pt/V ₂ O ₅	2.6	13.3	6	83	11	360	22
3	Pt/Nb ₂ O ₅	2.2	10.3	5	81	14	340	16
4	Pt/WO ₃	2.5	5.1	7	82	11	148	10
5	Pt/MoO_2	1.8	5.9	4	39	57	231	10
6	Pt/γ - Al_2O_3	2.6	3.9	0	31	69	107	0
7	Pt/TiO ₂	3.2	3.6	15	66	19	79	12
8	Pt/ZrO_2	2.7	2.5	12	39	49	62	8
9	Pt/CeO ₂	2.7	3.0	4	86	10	81	3
10	Pt/SiO ₂	2.6	1.5	0	39	61	42	0
11	Pt/ZnO	2.8	0.6	20	75	5	14	3
12	Pd/MoO_3	3.0^{f}	3.2	6	56	38	41	3
13	Re/MoO ₃	3.0^{f}	2.3	5	23	72	51	3
14	Ru/MoO ₃	3.0^{f}	0.9	37	50	13	12	4
15	Cu/MoO ₃ ^d	3.0^{f}	1.5	0	5	95	11	0
16	Cu/ZnO^d	30.0 ^f	0.4	19	12	69	9	0.3
17	$H_x MoO_{3-y}^{e}$	_	3.0	0	8	92	_	_
18	MoO_3	_	0.3	0	21	79	_	_

^a Reaction conditions: catalyst (50 mg), 1,4-dioxane (15 mL), $P_{\text{CO}_2} = 1.0 \text{ MPa}$, $P_{\text{H}_3} = 3.0 \text{ MPa}$, 200 °C, 20 h. Catalysts were reduced at 300 °C for 30 min in a flow of H_2 . ^b Determined by ICP analysis. ^c TON was calculated on the basis of total active metals contained in the catalysts. ^d Prepared by the wet impregnation method. ^e Synthesized by a solvothermal method according to ref. 44. ^f Nominal content.

Chemical Science

7%) (entries 2–4). For the Pt/ H_x MoO_{3– ν} catalyst, the turnover number (TON) calculated for CO2 conversion, based on the number of Pt atoms contained in the catalyst, was 1379, and the TON for methanol production was 462, demonstrating that the CO₂ hydrogenation reaction occurs in a catalytic manner. Interestingly, Pt supported on MoO₂ exhibited a lower CO₂ conversion (5.9%) and a lower methanol selectivity ($Sel_{MeOH} =$ 4%) compared with Pt/H_rMoO_{3-v} under the same conditions (entry 5). Pt catalysts supported on amphoteric oxides, such as Al₂O₃, TiO₂, ZrO₂, and CeO₂, exhibited low CO₂ conversions (entries 6-9) and low methanol selectivities. As the monocomponent counterparts, pristine MoO₃ (entry 18), defective $H_xMoO_{3-\nu}$ (prepared by a solvothermal method)⁴⁴ (entry 17) and Pt/SiO₂ catalyst (entry 10) were also examined; however, the CO₂ conversions (0.3%, 3.0% and 1.5%, respectively) over these catalysts in 20 h were far below that of the Pt/H_xMoO_{3-v} catalyst and the formation of methanol was not observed. It was thus clarified that the nature of the oxide support has a dramatic effect on the catalytic performance of the Pt catalyst in liquidphase CO₂ hydrogenation. In addition, Pd, Re, Ru, and Cu catalysts supported on MoO₃ (entries 12-15), which were prepared by a similar method (see Experimental section), and Cu/ZnO catalyst (entry 16; nominal Cu content = 30.0 wt%) traditionally used for gas-phase CO2 hydrogenation reaction showed low catalytic activities and low methanol yields under the conditions adopted in this study. The significantly low catalytic activity observed for the benchmark Cu/ZnO catalyst may be attributed to the use of organic solvent which is unmatched for Cu-based catalyst and a relatively lower operation temperature than that usually employed for Cu-based catalysts. These results indicate that Pt is an indispensable component in the catalytic reaction, and the synergetic effect

Liquid-phase CO_2 hydrogenation over molybdenum oxidesupported Pt catalyst

a high catalytic performance.

Fig. 1b shows the time variation of product yields during the reaction on the $Pt/H_xMoO_{3-y}(300)$ at 200 °C. CO was rapidly produced as the main product in the initial stage of the reaction

between Pt and Mo sub-oxide plays a critical role in achieving

and yields of methanol and methane steadily increased over time along with a gradual decrease in the yield of CO. The conversion of CO2 and the selectivity for methanol obtained at 200 °C after 120 h of reaction reached 41.4% and 71%, respectively, which corresponded to a 5.38 mmol yield of methanol (methanol production rate = 0.896 mmol $g_{\text{-cat}}^{-1} h^{-1}$). The decreased conversion rate of CO₂ in the latter stage of reaction may reflect the gradual reduction of CO₂/H₂ gas pressures inside the reactor. In methanol synthesis from CO2 and H₂, (i) the CO formation route and (ii) the HCOO⁻ (formate) formation route are known to be major reaction pathways. 6,45,46 Considering the product distribution and the fact that formate was not detected by liquid chromatography in the reaction solution, methanol is likely to be produced via the formation of CO as an intermediate (i.e. RWGS reaction), while a small fraction of CO is transformed irreversibly to methane.

Fig. 1c shows the effect of the loading amount of Pt on the catalytic activity. The highest yield and selectivity for methanol formation was achieved when the Pt loading was 1.3 wt%. Although the conversion of CO2 and the yield of methanol tended to increase with increasing Pt loading, they decreased when the Pt loading exceeded 1.5 wt%. Pt L3-edge XAFS analysis (Fig. S1 in ESI†) and Pt 4f XPS spectra (Fig. S2 in ESI†) verified that the Pt species on these catalysts exist as metallic Pt(0) NPs in all cases and the size of the Pt NPs increases with increasing Pt content. The catalytic activity was not directly proportional to the mean surface area of surface-exposed Pt atoms determined by CO pulse measurement (Fig. S3 in ESI†), suggesting that the CO₂ hydrogenation is catalyzed not solely on the Pt NPs surface, but at the interface between the Pt NPs and the H_xMoO_{3-v} support, and that larger Pt NPs are unfavorable due to a decrease in the number of Pt-H_xMoO_{3-v} interfacial sites.

Over the Pt/H_xMoO_{3-y}(300) catalyst, almost no product was detected in the absence of CO₂ (trace of CH₄ may be from carbonaceous species contained in the catalyst) (Table 2, entry 2). In fact, in an isotopic experiment using 13 CO₂ as a reaction gas instead of 12 CO₂, a signal at m/z = 33 assigned to 13 CH₃OH was detected (Fig. S4 in ESI†), confirming that CO₂ is the sole carbon source for CO, methanol and methane. More noteworthy is the fact that a substantial amount of CO was produced even in the absence of H₂ (entry 3). Considering that such a huge CO

Table 2 Methanol production via CO_2 hydrogenation using $Pt/H_xMoO_{3-y}(300)$ catalyst under different conditions^a

			Yield [µmol]			
Entry	Conditions	CO ₂ conv. [%]	МеОН	CO	CH_4	Total TON ^b
1	$P_{\rm CO_2} = 1.0 \; { m MPa}$ $P_{\rm H_2} = 3.0 \; { m MPa}$	25.0	1526	2501	532	1379
2	No CO_2 $P_{H_2} = 3.0 \text{ MPa}$	0	0	<1	66	_
3	$P_{ m H_2} = 1.0 \ m MPa$ No H ₂	10.9	0	1541	443	600
4	$P_{ ext{CO}_2} = 0.1 ext{ MPa} \ P_{ ext{H}_2} = 3.0 ext{ MPa}$	(CO conv.) 57.8	371	_	684	310

^a Reaction conditions: catalyst (Pt/ H_x MoO $_{3-y}$ (300), 50 mg), 1,4-dioxane (15 mL), 200 °C, 20 h. ^b TON was calculated on the basis of total Pt atoms contained in the catalyst.

evolution was not observed on most of the other supported Pt catalysts (Fig. S5 in ESI†), the oxygen vacancies created on H_x -MoO_{3-y} possibly functioned as deoxygenation sites to reduce CO₂ to CO. Furthermore, introduction of CO (0.1 MPa) instead of CO₂ resulted in the formation of substantial amounts of methanol and methane at 200 °C (entry 4), again confirming that methanol as well as methane are produced *via* hydrogenation of CO as an intermediate over the Pt/ H_x MoO_{3-y}(300) catalyst.

Structural analysis of Pt-loaded molybdenum oxide

The HR-TEM image of the $Pt/H_xMoO_{3-y}(300)$ catalyst revealed that the Pt NPs with an average particle size of 2.4 nm are uniformly immobilized on the Mo oxide particles (Fig. 2a).

In the enlarged HR-TEM image, the interplanar distance of the Pt NPs was *ca.* 1.95 Å, matching well the (200) plane of fcc Pt (Fig. 2b). The lattice fringes seen in the Mo oxide particle were not clear, being considerably disconnected or distorted in most cases (Fig. 2c). Only a few diffraction spots were observable in the selected electron diffraction (SAED) pattern (inset in Fig. 2c), indicating a short-range order atomic arrangement, which may be because of the introduction of many defect sites. Meanwhile,




Fig. 2 (a) HR-TEM image, (b–d) magnified HR-TEM images (inset shows the corresponding SAED patterns of the Pt/ H_x MoO_{3-y}(300)) catalyst, and (e) illustrations of the monoclinic $H_{0.9}$ MoO₃ crystal structure.

some clear lattice fringes were partly observed in some Mo oxide particles (Fig. 2d), which are consistent with the d-spacing of the (001) and (010) planes of the monoclinic $H_{0.9}MoO_3$ phase.⁴⁷⁻⁴⁹ The corresponding SAED pattern exhibited clear spots assignable to the (001) and (010) planes (inset in Fig. 2d). Two interplanar spacings were found to be 0.41 and 0.37 nm with a separation angle of 91–92°, which matched well with the monoclinic structure of the $H_{0.9}MoO_3$ phase with the $P2_1/c$ space group as shown in Fig. 2e, confirming the existence of crystalline $H_{0.9}MoO_3$ phases in the short-range order.

Interestingly, the catalytic activity of the $Pt/H_xMoO_{3-\nu}$ catalyst varied with the temperature of H2 reduction (Fig. 1d); both the CO₂ conversion and the yield of methanol tended to increase with increasing reduction temperature. In particular, the highest CO₂ conversion (25%) and methanol selectivity (33%) were attained when the catalyst was reduced at 300 °C. However, a marked drop of catalytic performance (conv. = 17.1%, $Sel_{MeOH} = 19\%$) was observed for reduction at 400 °C. H₂-TPR is commonly used to help understand the reduction behavior of metal oxides. Fig. 3a compares the H₂-TPR profiles of the as-synthesized oxide-supported Pt catalysts. The asprepared Pt/MoO₃ sample gave an intense reduction peak at 136 °C, while such a large H₂ consumption was not observed for the other oxide-supported Pt catalysts. The amount of H2 consumed below 200 °C was calculated to be 4.95 mmol-H2 per g-catalyst. The molar ratio of H atoms consumed per mole of Pt atoms contained in the catalyst (H/Pt) was 149 and that used per mole number of Mo atoms (H/Mo) was 1.44, whereas the asprepared Pt/SiO₂ showed a quite low consumption of H₂ (H/Pt molar ratio of 2.2). This result indicates that the large H2 consumption on Pt/MoO3 at around 136 °C is not only due to the reduction of the Pt precursor but is attributed to the reduction of the MoO₃ support. An additional H₂ consumption at around 280 °C may be associated with the formation of oxygen vacancies, as will be discussed later. Importantly, pristine MoO3 exhibited no H2 consumption below 500 °C, indicating that Pt assists in the reduction of the MoO3 support by facilitating the dissociation of molecular H2 (namely, the Hspillover process). Such a high reactivity of intracrystalline oxygen atoms in MoO₃ may well be responsible for the high CO₂ hydrogenation performance.

To track the crystallographic changes occurring with H₂ reduction at the different temperatures, XRD measurements were performed (Fig. 3b). The diffraction patterns of Pt/H_x- $MoO_{3-\nu}(100)$ were assigned to orthorhombic α -MoO₃ (PDF #5-0508) and monoclinic H_{0.9}MoO₃ (PDF #53-1024), while the peaks of unreduced Pt/MoO₃ were all indexed to orthorhombic α -MoO₃. Pt/H_xMoO_{3-v}(200) showed dominant peaks assigned to H_{0.9}MoO₃ with decreased diffraction intensities, and Pt/H_x- $MoO_{3-\nu}(300)$ exhibited almost no distinct diffractions, indicating a collapse of the H_{0.9}MoO₃ phase and a disordered atomic arrangement (the H_{0.9}MoO₃ phase may partly exist, as observed by HR-TEM). The orthorhombic α -MoO₃ used as a support in this study is composed of edge-sharing MoO₆ octahedra bilayers stacked along with [010] due to van der Waals interaction. 50,51 As demonstrated in many previous studies, H-spillover occurs on noble metal catalysts supported





Fig. 3 (a) H_2 -TPR profiles of Pt catalysts supported on various metal oxides. (b) XRD patterns, (c) Mo 3d XPS spectra, and (d) O 1s XPS spectra of unreduced Pt/MoO₃ and Pt/H_xMoO_{3-y} catalysts reduced with H_2 at different temperatures.

on reducible metal oxides in the presence of H_2 , in which molecular H_2 is dissociated over the noble metal NPs surface $(H_2 \rightarrow 2H^+ + 2e^-)$ and thus protons (H^+) and free electrons are concurrently injected into the metal oxide matrices. ^{52,53} In the case of the combination of the Pt NPs and α -MoO₃, H_2 dissociation occurs on the Pt NPs at around 140 °C (as shown in the H_2 -TPR, see Fig. 3a), and the dissociated H^+ atoms are coordinated to the interlayer terminal oxygen atoms to form hydroxyl groups, which yields a class of H_x MoO₃ materials (0 < x < 2), namely, hydrogen molybdenum bronze, ⁴⁷⁻⁴⁹ as depicted in the schematic of Scheme 1. During this H-spillover process, the free electrons are trapped by Mo^{6+} ions $(Mo^{6+} + e^-/2e^- \rightarrow Mo^{5+}/Mo^{4+})$, and thus a great number of low-valence Mo species are generated. The relevant intercalation chemistry on α -MoO₃ is already well established by earlier studies. ^{41-43,54-57} A further

temperature increase to 200-300 °C causes dehydration of H_xMoO₃ (as shown in the H₂-TPR, see Fig. 3a), in which lattice oxygen atoms (mainly bi-bridging oxygen atoms) are easily expelled by the H⁺ ions $(2H^+ + 2e^- + O_O \rightarrow V_O + H_2O)$, 58,59 thus resulting in a further greater reduction of H_xMoO₃ to the quasistable H_xMoO_{3-v} sub-oxide which has abundant oxygen vacancies. Introduction of massive amounts of oxygen vacancies causes order-disorder transitions in the metal oxide (as illustrated in Scheme 1), which accounts for the significantly decreased diffraction intensities for Pt/H_xMoO_{3-v}(200) and Pt/ $H_xMoO_{3-\nu}(300)$. As previously reported, the intercalation of H atoms and the introduction of oxygen vacancies into the MoO3 matrix increases the electron density of the entire oxide particle, fills the 4d Mo level, and brings about new energy levels near the conduction band (CB), which consequently leads to the emergence of new absorption bands due to surface plasmon resonance (SPR).41,60-62 This was corroborated by UV-vis-NIR measurement (Fig. S6 in ESI†), in which a strong absorption across the visible to NIR region with an intense SPR peak was observed for the reduced samples, while a limited absorption in the UV region was observed for the unreduced Pt/MoO₃ sample. Further increase in the reduction temperature to 400 °C led to the transition to the MoO2 phase, which has a distorted monoclinic rutile structure.

The intercalation of H atoms and the formation of oxygen vacancies within the Mo oxide matrices upon H2 reduction was corroborated by XPS measurement. From the Mo 3d XPS spectrum (Fig. 3c), it was confirmed that low-valence Mo species (Mo⁵⁺/Mo⁴⁺) were formed after H₂ reduction, while Mo⁶⁺ species mainly existed before reduction. The concentrations of these low-valence Mo species increased with rise in the reduction temperature. The proportion of these low-valence Mo species was determined as: Mo⁵⁺ 42.7%, Mo⁴⁺ 3.8% (100 °C reduction) \rightarrow Mo⁵⁺ 47.6%, Mo⁴⁺ 8.2% (200 °C reduction) \rightarrow Mo⁵⁺ 42.0%, Mo⁴⁺ 23.7% (reduction at 300 °C), suggesting that generation of Mo⁴⁺ mainly results from the formation of an oxygen vacancy.⁶³ A similar reduction behavior for Mo species and the introduction of oxygen vacancies were corroborated by inspection of the Mo K-edge X-ray absorption near edge structure (XANES) spectra and the Fourier transforms of extended XAFS (EXAFS)



Scheme 1 Schematic illustration of the crystallographic changes of Pt/H_xMoO_{3-v} upon H_2 reduction.

spectra, respectively (see Fig. S7 in ESI; † see also Fig. 5). In the O 1s XPS spectra (Fig. 3d), unreduced Pt/MoO₃ exhibited two main peaks which are ascribed to lattice oxygen (O_{latt}; 530.5 eV) and surface hydroxyl groups (O_{-OH}; 532.3 eV). Note that the samples were introduced to the XPS analysis chamber without exposure to the air, thereby excluding the possibility of adsorbed oxygen species. For the series of Pt/H_xMoO_{3-y} samples, the peak for the O_{-OH} species increased in intensity, and additional tailings, assigned to the formation of OH₂ groups weakly coordinated to Mo atoms (O_{-OH}₂), were observed at the higher binding energy region at about 533.6 eV. The proportion of these hydroxyl species ((O_{-OH} + O_{-OH}₂)/O_{total}) was found to increase significantly upon H₂ reduction (unreduced Pt/MoO₃ (20.3%) \rightarrow Pt/H_xMoO_{3-y} (41-49%)), evidencing the H⁺-intercalation upon H₂ reduction process.⁶⁴

The above results verify the co-existence of the intercalated H atoms and oxygen vacancies in Pt/H_xMoO_{3-y} , which accompanies the formation of low-valence Mo species. To quantify the amounts of doped H atoms and oxygen vacancies, TG analysis was performed.^{65,66} Upon heat treatment of oxygen-defective H_xMoO_{3-y} in an inert gas flow, a dehydration reaction may occur through eqn (1):

$$H_x MoO_{3-\nu} \to MoO_{3-\nu-x/2} + 1/2x H_2O$$
 (1)

However, upon heat treatment in an air gas flow, both the dehydration reaction and a filling of the oxygen vacancies to form molybdenum trioxide (MoO₃) possibly occur through eqn (2):

$$H_x MoO_{3-y} + O_2 (air) \rightarrow MoO_3 + 1/2x H_2O$$
 (2)

Therefore, the stoichiometry of the doped H atoms (x) and the oxygen vacancies (y) in H_xMoO_{3-y} can be calculated from the changes in thermal weight observed under the two different conditions (Fig. S8 in ESI†). Assuming the composition of the oxygen-defective molybdenum oxide of H_xMoO_{3-y} , the composition was determined as $H_{1.76}MoO_{2.99}$ (100 °C reduction) \rightarrow $H_{1.15}MoO_{2.72}$ (200 °C reduction) $\rightarrow H_{0.35}MoO_{2.26}$ (300 °C reduction) from the results of TG analysis, showing that the intercalated H atoms are continuously removed via thermal dehydration, while an increased number of oxygen vacancies is introduced after H2 reduction at elevated temperatures. As shown in Fig. 1d, the CO₂ conversion and the yield of methanol increased along with an increase in the stoichiometry of the oxygen vacancy (y) in the Pt/H_xMoO_{3-v}(T) catalysts in the reduction temperature range of 100 to 300 °C. It should be mentioned that the stoichiometry of x and y in the Pt/H_x - $MoO_{3-\nu}(400)$ catalyst was almost equal to 0.0 and 1.0, respectively, indicating the formation of MoO2, which is consistent with XRD data (Fig. 3b). The decreased activity for Pt/H_x- $MoO_{3-\nu}(400)$ is probably attributed to the transition to monoclinic MoO₂ with less oxygen vacancies. These results indicate the possibility that the oxygen vacancies formed in the quasistable H_xMoO_{3-y} sub-oxide during H₂ reduction play a pivotal role in the CO2 hydrogenation and in the production of methanol.

Understanding the role of the oxygen vacancy

 ${\rm CO_2}$ adsorption is generally regarded as being a prerequisite in the ${\rm CO_2}$ reduction process. Based on the above experiments, it may be hypothesized that the presence of abundant surface oxygen vacancies endows the ${\rm Pt/H_xMoO_{3-y}}$ with enhanced ${\rm CO_2}$ adsorption, leading to an efficient activation of ${\rm CO_2}$ on the surface. This was verified by the ${\rm CO_2}$ adsorption measurement (Fig. S9 in ESI†). The ${\rm Pt/H_xMoO_{3-y}(300)}$, which possessed the highest oxygen vacancy concentration, showed a much higher ${\rm CO_2}$ adsorption capacity than the unreduced ${\rm Pt/MoO_3}$.

To understand the role of the oxygen vacancy at an atomic level, the CO₂ adsorption energies over the surface of oxygendefective and perfect molybdenum oxide were calculated using density function theory (DFT) calculations. Considering the layered structure of $H_{0.9}MoO_3$ in the Pt/ H_xMoO_{3-y} catalyst, the (100) surface of H_{0.9}MoO₃ was chosen to construct the slab model. For oxygen-defective slab model, oxygen vacancy was created at the bi-bridging oxygen atom position.58,59 The adsorption energy of CO2 on the oxygen-defective H30Mo32O95 surface was calculated to be -8.3 kcal mol⁻¹, which was significantly higher than that on the perfect H₃₀Mo₃₂O₉₆ surface $(-0.23 \text{ kcal mol}^{-1})$, indicating that an oxygen defect site is favorable for adsorption of CO2.67,68 When CO2 is adsorbed at the oxygen vacancy site, the CO2 molecule becomes bent, and the O-C-O angle changes from 179.2° to 125.1°, and the C-O bond length is extended from 1.178 Å to 1.224/1.370 Å (Fig. 4a), while those adsorbed on the perfect surface were unchanged (Fig. 4b).68 These findings indicate that the C-O bonds are weakened on the oxygen-defective H₃₀Mo₃₂O₉₅ surface. Furthermore, Mulliken population analysis demonstrated that the total charge (Δq) of CO₂ is increased from +0.0e (on perfect $H_{30}Mo_{32}O_{96}$) to -0.47e (on oxygen-defective $H_{30}Mo_{32}O_{95}$). The CO2 molecule adsorbed on an oxygen vacancy gains more electrons from the low-valence Mo ions (i.e. Mo⁵⁺/Mo⁴⁺ species) with partially higher electron densities, which leads to polarization of CO2, which, therefore, promotes the activation and dissociation of the CO2 molecule.

To understand the catalytic role of the oxygen vacancy in CO₂ hydrogenation, *in situ* XAFS measurement was performed.




Fig. 4 Optimized structure models for CO_2 adsorbed on (a) oxygen-defective H_xMoO_{3-y} ($H_{30}Mo_{32}O_{95}$) surface and (b) perfect H_xMoO_3 ($H_{30}Mo_{32}O_{96}$) surface.




Fig. 5 (a) In situ Mo K-edge XANES spectra of Pt/MoO $_3$ measured at 200 °C; before H $_2$ reduction (black line), after H $_2$ reduction under a flow of 20% H $_2$ /He (red line), after subsequent flow of 20% CO $_2$ /He (blue line) and subsequent flow of 20% H $_2$ /He (orange line). (b) Change of valence state of the Mo species during the in situ XAFS measurement. The valence state was determined by a linear interpolation method

Fig. 5a shows the XANES spectra in the Mo K-edge region for the as-prepared Pt/MoO₃ sample before and after H₂ reduction at 200 °C, and for those measured after subsequent exposure to H2 and CO₂ at 200 °C. The as-prepared Pt/MoO₃ sample exhibited an absorption spectrum with a characteristic pre-edge absorption at 20 006 eV, which was almost the same as that of orthorhombic α-MoO₃. After H₂ reduction at 200 °C, the pre-edge absorption was significantly diminished and the absorption edge position clearly shifted towards the lower energy region, which led to an absorption spectrum close to that of monoclinic MoO₂. This is because of the phase transition from the orthorhombic α-MoO₃ with a distorted octahedral geometry to the H_xMoO_{3-y} sub-oxide with a symmetric octahedral geometry and low-valence Mo atoms. 69,70 Such a spectral change upon H₂ reduction is consistent with the results of XRD and Mo 3d XPS. After the introduction of the 20% CO₂/He flow gas at 200 °C, the absorption edge shifted slightly towards the higher energy region, showing substantial oxidation of Mo species with CO2. The subsequent switching to 20% H₂/He flow caused an absorption edge shift back towards the lower energy region, indicating a re-reduction of Mo species with H2. The average valence state of Mo ions in the catalyst during the in situ XAFS measurement was determined from the absorption edge position (E_0) using a linear interpolation method and was plotted as a function of time. As shown in Fig. 5b, the average valence state of Mo increased/decreased reversibly for the CO2/H2 flow at 200 °C, clearly demonstrating that a redox event involving the Mo species took place during reduction of CO2. The molybdenum oxide is initially reduced by H atoms dissociated on Pt NPs through a H-spillover process to produce oxygen vacancies. The CO₂ molecule is adsorbed and activated at the oxygen vacancy interbedded between the under-coordinated Mo (Mo⁵⁺/ Mo⁴⁺) sites, which leads to the formation of CO and a concurrent replenishment of the oxygen vacancy $(CO_2 + V_O \rightarrow CO + O_O)$ accompanied by the oxidation of Mo atoms. This was also corroborated by Mo 3d XPS spectra, in which the proportion of Mo⁴⁺ species considerably decreased and the average oxidation number of Mo increased upon a treatment with 1.0 MPa CO2 at 200 °C (Fig. S10 in ESI†). In the presence of H2, the oxygen




Fig. 6 In situ differential DRIFT spectra of adsorbed species on (a) Pt/ $H_xMoO_{3-v}(300)$ catalyst and (b) pristine MoO_3 .

vacancy can be regenerated by the reaction with H atoms, thus the catalytic cycle can be achieved. This process can be understood as an oxygen-vacancy-mediated "reverse Mars–van Krevelen $(M-vK)^{71}$ " mechanism. 31,33,41,72 Thus, DFT calculations and *in situ* XAFS measurement revealed that the oxygen vacancy sites in oxygen-defective H_xMoO_{3-y} not only stabilize CO_2 by donating electrons, but also promote dissociation of CO_2 through electron transfer from the abundant localized electrons on the ionic $Mo (Mo^{5+}/Mo^{4+})$ species to CO_2 , which should be effective for promoting the cleavage of CO_2 and the subsequent hydrogenation reactions.

The CO₂ hydrogenation mechanism

To monitor the CO_2 hydrogenation process, *in situ* DRIFT experiments were performed (Fig. 6). Prior to DRIFT spectra measurement, the as-synthesized Pt/MoO₃ sample was pretreated under H₂ flow for 30 min at 300 °C to yield Pt/H_x-MoO_{3-y}(300), followed by cooling to 250 °C, and then 1.0 MPa of CO_2 and 2.0 MPa of H₂ were successively introduced.

After the introduction of CO2, two distinct peaks were observed at 1404 and at around 1530 cm⁻¹, the former being commonly assigned to symmetric stretching vibration mode of monodentate carbonate species ($\nu_s(OCO^-)$) (major species) and the latter being characteristic of the C=O stretching vibration of bidentate carbonates (minor species).23,73-75 After the introduction of H2, a broad band assignable to gaseous CO was observed at around 2130 cm⁻¹,74-76 indicating that the CO₂ adsorbed on the catalyst underwent deoxygenation to produce CO, although such a peak was not observed before H2 introduction because of only a small yield of CO. Along with the increase in time, several additional features associated with the hydrogenated products were observed with increased IR intensity; the peaks observed at 2851 and 2922 cm⁻¹ are assignable to stretching vibrations of C-H bond.76,77 The tailing band observed at around 1300-1400 cm⁻¹ is assignable to hydroxyl O-H deformation vibration and CH₃ deformation vibration. The emergence of these bands indicate the formation of methanol over the Pt/H_xMoO_{3-v}(300) catalyst via hydrogenation of activated CO2 intermediates or gaseous CO. IR bands associated with formate intermediates were not detected by in situ DRIFT

Edge Article

y = 0.532x + 2.089y = 0.380x - 0.787 -0.5 0.0 0.0 0.5 10 MeOF Yield of products / 600 -8.547x + 18.833 400 772x + 17.6032.15 2.20 2.25 200

Fig. 7 (a) Double logarithm plots of reaction rate (R) and the partial pressure of CO₂ (P_{CO_2}), (b) double logarithm plots of reaction rate (R) and the partial pressure of H₂ (P_{H_2}), (c) effect of reaction temperature on catalytic performance, and (d) Arrhenius plots for the Pt/H_x-MoO_{3-y}(300) catalyst. Reaction conditions: catalyst (50 mg), 1,4-dioxane (15 mL), reaction time = 2 h.

1000/T / K

analysis, again elucidating that hydrogenation of CO_2 on Pt/H_xMoO_{3-y} catalyst occurs via the "RWGS-CO pathway". It is also noteworthy that CO/methanol were produced even in the absence of solvent, demonstrating the availability of Pt/H_x-MoO_{3-y} catalyst in gas-phase CO_2 hydrogenation reaction to produce CO/methanol. In contrast, the intensity of the IR band for CO_2 adsorbed on pristine MoO_3 was apparently less than that adsorbed on $Pt/H_xMoO_{3-y}(300)$, indicating a much larger amount of adsorption sites for CO_2 exists on $Pt/H_xMoO_{3-y}(300)$. Furthermore, the IR bands associated with the hydrogenated carbon products were scarcely observed on pristine MoO_3 , demonstrating the role of Pt NPs as a hydrogenation center.

The reaction rate (R) of CO₂ hydrogenation can be expressed by $R = k \times P_{\text{CO}_2}^{\ \ \alpha} \times P_{\text{H}_2}^{\ \ \beta}$, where k is the rate constant, P_{CO_2} and

 $P_{\rm H_2}$ represent the partial pressure of ${\rm CO_2}$ and ${\rm H_2}$, and α and β represent the reaction order of CO₂ and H₂, respectively. Kinetic analyses demonstrated that the reaction order of $CO_2(\alpha)$ for CO production (0.532) was apparently larger than those for methanol production (0.363) and CH₄ production (0.380), indicating that the CO formation step is primarily governed by the CO₂ pressure and H₂ is rarely involved in this step. However, the reaction orders of $H_2(\beta)$ for methanol production (1.847) and CH₄ production (0.671) were much larger than that for CO production (0.209), indicating that methanol and CH₄ are produced from a CO intermediate via hydrogenation and the methanol production rate is strongly dependent on the H2 pressure. These results are consistent with the conclusions drawn by catalytic experiments and the in situ DRIFT spectra measurement whereby CO is produced via deoxygenation of CO2 at the oxygen vacancy sites and methanol and CH4 are produced via hydrogenation of the CO on the Pt NPs. Furthermore, the reaction order of $H_2(\beta)$ for methanol production (1.847) was close to 2, which is consistent with the stoichiometric ratio of the CO hydrogenation reaction to produce methanol (CO + 2H₂ → CH₃OH). Reaction rates decreased as the reaction temperature was lowered (Fig. 7c), although methanol synthesis from CO2/H2 favors lower reaction temperature due to an exothermic reaction. This is probably because of the RWGS reaction, an endothermic process (CO2 + $H_2 = CO + H_2O$; $\Delta H_{298}^0 = 41.2 \text{ kJ mol}^{-1}$), dominantly takes place in the early stage of reaction. From the Arrhenius plots, the activation energies for the production of CO, methanol, and CH_4 were determined as 46.8, 71.1, and 72.9 kJ mol⁻¹, respectively (Fig. 7d), verifying that the former deoxygenation reaction of CO₂ to produce CO is energetically more favorable than the latter hydrogenation reactions of the CO intermediate.

To draw a possible reaction pathway for CO_2 hydrogenation whereby methanol is produced over the Pt/H_xMoO_{3-y} catalyst, DFT calculations using the periodic slab model were performed. Based on the HR-TEM observation results and previous literature, ^{42,43} a slab model composed of a Pt_{20} cluster immobilized on the (100) exposed surface of $H_{30}Mo_{32}O_{96}$ of which the





Fig. 8 Optimized reaction pathway for CO_2 hydrogenation to produce methanol, and potential energy diagram obtained by DFT calculation using $H_{26}Mo_{32}O_{96}-Pt_{20}$ slab model and schematic illustrations of the corresponding structure models in each reaction step.

interface is bridged by four Mo-O-Pt bonds was established (state A in Fig. 8). The calculated stepwise energy diagrams for CO₂ hydrogenation to methanol are depicted in Fig. 8 (the optimized structure models for each reaction step are presented in Fig. S11 in ESI†). Note that all the presented intermediate states were optimized after considering multiple possible pathways with the lowest energies. To begin with, three H₂ molecules are adsorbed into the slab model, which results in the formation of six dissociated H atoms on the Pt20 cluster resulting in a large stabilization energy due to exothermic process (state B). The thus formed active H atoms are transferred to nearby surface terminal O atoms (states C, D), and then coordinated to the bi-bridging oxygen atom (states E, F), which eventually leads to the formation of H₂O (state G) and an oxygen vacancy (state H) $(2H^+ + 2e^- + O_O \rightarrow H_2O + V_O)$, coinciding well with the previous reports of O vacancy formation on α-MoO₃. 58,59 The above reaction steps proceed with relatively low activation energies (TS1 \sim TS5; E_a < 28 kcal mol⁻¹) compared with the later reaction steps, while no possible pathways were found over a H₃₀Mo₃₂O₉₆ slab model without the Pt₂₀ cluster. Thus, an oxygen vacancy is likely to be formed via the Hspillover process involving the Pt NPs as illustrated in Scheme 1.

Next, one CO2 molecule is adsorbed nearby the oxygen vacancy site (state I). As demonstrated for the oxygen-defective H₃₀Mo₃₂O₉₅ slab model (Fig. 4a), CO₂ is adsorbed and coordinated on the oxygen vacancy (state J) with an energy barrier of 46.0 kcal mol⁻¹ (**TS6**) to form the monodentate carbonate species (*O-C-O) or bidentate carbonate species (CO₃²⁻) as intermediates, which is well consistent with the results obtained above whereby the oxygen vacancy is responsible for capturing and activating CO2. The dissociation of the C=O bond of these intermediates occurs on the O vacancy site with an energy barrier of 20.1 kcal mol⁻¹ (TS7), and the dissociated *CO is stabilized by being adsorbed on the Pt20 cluster (state K). The C=O bond cleavage on O vacancy site is corroborated by comparing the reaction paths on the different sites; over the perfect slab model without an oxygen vacancy, CO2 molecule is stabilized most by being adsorbed on the Pt20 cluster surface, and the path for *CO formation could not be explored. The



Scheme 2 Proposed reaction mechanism of CO_2 hydrogenation to produce methanol over the Pt/H_xMoO_{3-y} catalyst.

dissociation of CO_2 on the Pt_{20} cluster surface was found to involve a high energy barrier of 102.1 kcal mol^{-1} (Fig. S12 in ESI†), which is 5-fold higher than that on the O vacancy site, indicating a low possibility of CO_2 dissociation on the Pt surface. Thus, the oxygen vacancy of H_xMoO_{3-y} lowers the energy barriers for the cleavage of the C=O bond and functions as a deoxygenation center, rendering the Pt/H_xMoO_{3-y} catalyst highly active towards CO_2 hydrogenation.

Subsequently, the *CO intermediate adsorbed on the Pt₂₀ cluster is hydrogenated by the active H atoms to finally produce methanol. The H atom on Pt first adds to the oxygen atom of the *CO (state L), which is followed by successive hydrogenation of the *COH intermediate to form *CHOH (state M), *CH₂OH (state N), and finally to produce the desired *CH₃OH (state O). The hydrogenation of *CO into *COH, *CHOH, *CH₂OH and *CH₃OH involves high energy barriers of 75.2, 13.2, 58.3, and 64.1 kcal mol⁻¹, respectively. In particular, the addition of the first H atom to *CO is required to overcome the highest energy barrier among all the TS's. This result suggests that CO serves as the main intermediate, and the rate-determining step of this reaction is the hydrogenation of the *CO intermediate (TS8), this being consistent with the reaction results and the kinetic analysis (Fig. 7).

We further explored the reaction paths for the production of CO and methane over the same slab model. Free CO can be formed from the *O-C-O intermediate with an energy barrier of 15.4 kcal mol⁻¹ (TS7') (for optimized structure models, see Fig. S13 in ESI†), which is slightly lower than the energy barrier for the formation of the *CO intermediate adsorbed on the Pt20 cluster (TS7: $E_a = 15.4 \text{ kcal mol}^{-1}$) and is significantly lower than those for methanol production from the *CO intermediate (TS8, TS10, TS11). This result indicates that gaseous CO formation is thermodynamically more favorable than the formation of methanol, being in line with the experimental results. Regarding methane production via hydrogenation of the *CO intermediate, possible intermediates and reaction pathways over the H₂₆Mo₃₂O₉₆-Pt₂₀ model were screened for. Given that the energy barrier for dehydration of *CHOH to form *CH ($E_a = 65.4 \text{ kcal mol}^{-1}$) was lower than those for dehydration of *COH ($E_a = 67.7 \text{ kcal mol}^{-1}$) and *CH₂OH ($E_a =$ 118.3 kcal mol⁻¹), *CH is considered as the stable intermediate upon the formation of methane on the Pt/H_xMoO_{3-y} catalyst (Fig. S14 in ESI†). The following hydrogenation of *CH proceeds via a stepwise formation of *CH₂, *CH₃ and CH₄ with reaction barriers of 20.1, 36.2 and 54.8 kcal mol^{-1} , respectively. The highest energy barrier to generate methanol from the *CHOH intermediate is 64.1 kcal mol⁻¹, which is lower than that for the transformation into methane ($E_a = 65.4 \text{ kcal mol}^{-1}$). Thus, methanol formation is energetically more favorable than methane formation over the Pt/H_xMoO_{3-y} catalyst; hence the higher selectivity for methanol rather than for methane being well elucidated as demonstrated in the reaction experiments.

Based on comprehensive analyses of the reactions, *in situ* spectroscopic measurements and DFT calculations, we conclude that CO₂ hydrogenation to produce methanol over the Pt/H_xMoO_{3—y} catalyst is achieved *via* oxygen vacancy-mediated "reverse Mars–van Kreveren" mechanism, ^{31,33,41,72} as illustrated

in Scheme 2. First, oxygen vacancies are formed in the H_x-MoO_{3-v} sub-oxide during H₂ reduction through H₂ dissociation on the Pt NPs and the H-spillover process (steps 1 and 2). CO2 is adsorbed on the oxygen vacancies and activated by the adjacent under-coordinated low-valence Mo centers (Mo⁵⁺/Mo⁴⁺) via electron donation with high adsorption energy, which induces the polarization of CO₂, weakening and then dissociation of the C=O bond. As a result, a CO intermediate is formed, and the oxygen vacancy is concurrently replenished with O atoms to restore an intact oxide surface (step 3). Based on the exploration by DFT calculation, the *CO intermediate is likely to migrate onto the Pt NP surface (step 4). The *CO intermediate reacts with active H species dissociated on the Pt NPs to initially form *COH species, which then undergo stepwise C-H bond formation, finally leading to the formation of methanol (step 5). A sole H_xMoO_{3-y} works as a "reductant" but cannot be deemed as a "catalyst" for CO2 reduction. On the contrary, the hybrid Pt/ $H_xMoO_{3-\nu}$ catalyst developed in this study contains Pt NPs, which act as (i) active sites to supply dissociated H atoms to generate oxygen vacancies in Mo oxide and as (ii) active sites for hydrogenation of the CO intermediate to finally produce methanol (and methane). Owing to the high H₂ dissociation ability of the Pt NP (which occurs at around 140 °C, see Fig. 3a), the catalyst can sustain oxygen vacancies, and thus the catalytic cycle can be realized (steps 1 and 2). These catalytic cycles and the cooperative effect at the Pt-H_xMoO_{3-v} interface facilitate efficient CO2 hydrogenation under relatively mild reaction conditions. 38,74,75 The proposed reaction mechanism is totally different from the one known for the conventional Cu-based catalysts which normally require much higher reaction temperatures.39,45,46

In addition, recyclability of the Pt/H_xMoO_{3- ν}(300) catalyst was investigated in recycling tests (Fig. S15 in ESI†). The Pt/ $H_xMoO_{3-\nu}(300)$ retained its catalytic activity for methanol production over multiple cycles; however, a continuous reduction of activity and methanol yield was observed. Characterization data including the XRD, XPS and XAFS results demonstrated that the structural variation of the H_xMoO_{3-y} support was negligible even after the fourth cycle (see Fig. S16 in ESI†); however, TEM observation showed that the average Pt particle diameter of the spent catalyst apparently increased. As demonstrated above, the CO₂ deoxygenation is the dominant reaction at the interface between the Pt NPs and the $H_xMoO_{3-\nu}$ sub-oxide. Therefore, the reason for the continuous reduction in activity is probably due to the decreased number of Pt-H_x- $MoO_{3-\nu}$ interfacial sites due to the aggregation of the Pt NPs upon catalytic use,78 hence making the cooperative effect less effective.

Conclusions

In conclusion, the Pt/H_xMOO_{3-y} hybrid catalyst was demonstrated to function as an efficient catalyst for CO_2 hydrogenation to produce methanol under relatively mild reaction conditions. The Pt NPs immobilized on a quasi-stable H_x - MoO_{3-y} sub-oxide exhibited the highest CO_2 conversion and methanol yield among the oxide-supported Pt catalysts

examined, with a methanol formation rate of 1.53 mmol g_{-cat}⁻¹ h⁻¹ in the liquid-phase CO₂ hydrogenation under relatively mild reaction conditions (total 4.0 MPa, 200 °C). Comprehensive analyses revealed that abundant surface oxygen vacancies and redox ability of Mo species in quasi-stable H_xMoO_{3-v} endows this catalyst with enhanced adsorption and activation of CO₂ to produce a CO intermediate. As a result, the Pt NP can act as (i) a hydrogenation center to produce methanol from *CO species and as (ii) a site to supply active H atoms to regenerate oxygen vacancies via the H-spillover process. Thus, it has been clarified that CO_2 hydrogenation on the Pt/H_xMoO_{3-y} catalyst is governed by the oxygen-vacancy-mediated "reverse Mars-van Krevelen" mechanism, which is promoted by the synergetic interaction between reducible Mo oxide as a CO2-activation center and Pt NP as a H2-activation center. For future development with the aim of large-scale implementation, further efforts to improve the reusability as well as to reduce the cost of the catalyst/process are needed. We expect that a continuous production of methanol/CO with a higher methanol selectivity is possible by employing a gas-phase fixed-bed reactor system, which can circumvent some problems in liquid-phase batch reactor system, such as catalyst deactivation, solvent use and post-separation process. The insights gained in this study is expected to provide a new avenue for manipulating catalytic properties via "oxygen vacancy engineering" approach and for advancing the mechanistic understanding of heterogeneous catalysis involving oxygen vacancies of metal oxides, which would contribute to the future development of more elaborated and high-performance catalysts for CO₂ hydrogenation.

Author contributions

Y. Kuwahara led the conceptualization, design of the experiments, analysis and validation of the results, and wrote the manuscript. T. Mihogi, K. Hamahara and K. Kusu contributed to material synthesis, data collection, and formal analysis. H. Kobayashi contributed to the DFT calculation, formal analysis and data curation. H. Yamashita provided key advice and supervised the study.

Conflicts of interest

There are no conflicts to declare.

Acknowledgements

The present work was supported by JST, PRESTO (grant no. JPMJPR19T3), Japan, the Tonen General Sekiyu Research/Development Encouragement & Scholarship Foundation, and the Iwatani Naoji Foundation. A part of this work was supported by the grant for research of the Japan Petroleum Institute, 2018, awarded to Y. K. Y. K. and H. Y. thank Element Strategy Initiative of MEXT (grant no. JPMXP0112101003). The synchrotron radiation experiments for XAFS measurements were performed at the BL01B1 beam line in SPring-8 with the approval from JASRI (no. 2018B1185 and 2019A1050).

Notes and references

- 1 J. Artz, T. E. Muller, K. Thenert, J. Kleinekorte, R. Meys, A. Sternberg, A. Bardow and W. Leitner, *Chem. Rev.*, 2018, 118, 434–504.
- 2 A. J. Hunt, E. H. Sin, R. Marriott and J. H. Clark, *ChemSusChem*, 2010, 3, 306–322.
- 3 E. V. Kondratenko, G. Mul, J. Baltrusaitis, G. O. Larrazábal and J. Pérez-Ramírez, *Energy Environ. Sci.*, 2013, **6**, 3112–3135.
- 4 E. A. Quadrelli, G. Centi, J. L. Duplan and S. Perathoner, *ChemSusChem*, 2011, 4, 1194–1215.
- 5 A. Alvarez, A. Bansode, A. Urakawa, A. V. Bavykina, T. A. Wezendonk, M. Makkee, J. Gascon and F. Kapteijn, *Chem. Rev.*, 2017, 117, 9804–9838.
- 6 M. D. Porosoff, B. Yan and J. G. Chen, *Energy Environ. Sci.*, 2016, 9, 62–73.
- 7 R. Sun, Y. Liao, S.-T. Bai, M. Zheng, C. Zhou, T. Zhang and B. F. Sels, *Energy Environ. Sci.*, 2021, 14, 1247–1285.
- 8 A. Karelovic, G. Galdames, J. C. Medina, C. Yévenes, Y. Barra and R. Jiménez, *J. Catal.*, 2019, **369**, 415–426.
- 9 R. P. Ye, J. Ding, W. Gong, M. D. Argyle, Q. Zhong, Y. Wang, C. K. Russell, Z. Xu, A. G. Russell, Q. Li, M. Fan and Y. G. Yao, *Nat. Commun.*, 2019, **10**, 5698.
- 10 Z. Ma and M. D. Porosoff, ACS Catal., 2019, 9, 2639–2656.
- 11 D. R. Palo, Chem. Rev., 2007, 107, 3992-4021.
- 12 K. C. Waugh, Catal. Lett., 2012, 142, 1153-1166.
- 13 M. Saito, Catal. Surv. Jpn., 1998, 2, 175-184.
- 14 G. A. Olah, Angew. Chem., Int. Ed., 2013, 52, 104-107.
- 15 G. A. Olah, A. Goeppert and G. K. S. Prakash, *J. Org. Chem.*, 2009, 74, 487–498.
- 16 R. Gaikwad, A. Bansode and A. Urakawa, *J. Catal.*, 2016, 343, 127–132.
- 17 W. H. Wang, Y. Himeda, J. T. Muckerman, G. F. Manbeck and E. Fujita, *Chem. Rev.*, 2015, **115**, 12936–12973.
- 18 Y. Chen, S. Choi and L. T. Thompson, *ACS Catal.*, 2015, 5, 1717–1725.
- 19 S. Kar, A. Goeppert, J. Kothandaraman and G. K. S. Prakash, ACS Catal., 2017, 7, 6347–6351.
- 20 J. Kothandaraman, A. Goeppert, M. Czaun, G. A. Olah and G. K. Prakash, J. Am. Chem. Soc., 2016, 138, 778–781.
- 21 N. M. Rezayee, C. A. Huff and M. S. Sanford, *J. Am. Chem. Soc.*, 2015, 137, 1028–1031.
- 22 S. Wesselbaum, V. Moha, M. Meuresch, S. Brosinski, K. M. Thenert, J. Kothe, T. V. Stein, U. Englert, M. Holscher, J. Klankermayer and W. Leitner, *Chem. Sci.*, 2015, 6, 693–704.
- 23 S. Bai, Q. Shao, Y. Feng, L. Bu and X. Huang, *Small*, 2017, 13, 1604311.
- 24 M. U. Khan, L. Wang, Z. Liu, Z. Gao, S. Wang, H. Li, W. Zhang, M. Wang, Z. Wang, C. Ma and J. Zeng, *Angew. Chem.*, *Int. Ed.*, 2016, 55, 9548–9552.
- 25 H. Li, L. Wang, Y. Dai, Z. Pu, Z. Lao, Y. Chen, M. Wang, X. Zheng, J. Zhu, W. Zhang, R. Si, C. Ma and J. Zeng, *Nat. Nanotechnol.*, 2018, 13, 411–417.
- 26 T. Toyao, S. Kayamori, Z. Maeno, S. M. A. H. Siddiki and K.-i. Shimizu, *ACS Catal.*, 2019, **9**, 8187–8196.

- 27 Z. He, Q. Qian, J. Ma, Q. Meng, H. Zhou, J. Song, Z. Liu and B. Han, *Angew. Chem., Int. Ed.*, 2016, **55**, 737–741.
- 28 X. Zheng, Y. Lin, H. Pan, L. Wu, W. Zhang, L. Cao, J. Zhang, L. Zheng and T. Yao, *Nano Res.*, 2018, 11, 2357–2365.
- 29 W. Zhang, L. Wang, H. Liu, Y. Hao, H. Li, M. U. Khan and J. Zeng, *Nano Lett.*, 2017, 17, 788–793.
- 30 K. W. Ting, T. Toyao, S. M. A. H. Siddiki and K.-i. Shimizu, *ACS Catal.*, 2019, **9**, 3685–3693.
- 31 D. Ferri, T. Bürgi and A. Baiker, *Phys. Chem. Chem. Phys.*, 2002, 4, 2667–2672.
- 32 G. Zhuang, Y. Chen, Z. Zhuang, Y. Yu and J. Yu, *Sci. China Mater.*, 2020, **63**, 2089–2118.
- 33 L. F. Bobadilla, J. L. Santos, S. Ivanova, J. A. Odriozola and A. Urakawa, *ACS Catal.*, 2018, **8**, 7455–7467.
- 34 B. J. Hare, D. Maiti, Y. A. Daza, V. R. Bhethanabotla and J. N. Kuhn, ACS Catal., 2018, 8, 3021–3029.
- 35 J. Ye, C. Liu, D. Mei and Q. Ge, ACS Catal., 2013, 3, 1296-1306.
- 36 G. Xi, S. Ouyang, P. Li, J. Ye, Q. Ma, N. Su, H. Bai and C. Wang, *Angew. Chem., Int. Ed.*, 2012, **51**, 2395–2399.
- 37 J. Li, Y. Ye, L. Ye, F. Su, Z. Ma, J. Huang, H. Xie, D. E. Doronkin, A. Zimina, J.-D. Grunwaldt and Y. Zhou, *J. Mater. Chem. A*, 2019, 7, 2821–2830.
- 38 J. A. Rodriguez, P. Liu, D. J. Stacchiola, S. D. Senanayake, M. G. White and J. G. Chen, ACS Catal., 2015, 5, 6696–6706.
- 39 K. Larmier, W. C. Liao, S. Tada, E. Lam, R. Verel, A. Bansode, A. Urakawa, A. Comas-Vives and C. Coperet, *Angew. Chem.*, *Int. Ed.*, 2017, 56, 2318–2323.
- 40 M. S. Frei, C. Mondelli, R. Garcia-Muelas, K. S. Kley, B. Puertolas, N. Lopez, O. V. Safonova, J. A. Stewart, D. Curulla Ferre and J. Perez-Ramirez, *Nat. Commun.*, 2019, 10, 3377.
- 41 Y. Kuwahara, Y. Yoshimura, K. Haematsu and H. Yamashita, J. Am. Chem. Soc., 2018, **140**, 9203–9210.
- 42 L. Chen, A. C. Cooper, G. P. Pez and H. Cheng, *J. Phys. Chem. C*, 2008, **112**, 1755–1758.
- 43 H. Cheng, L. Chen, A. C. Cooper, X. Sha and G. P. Pez, *Energy Environ. Sci.*, 2008, **1**, 338–354.
- 44 H. Cheng, T. Kamegawa, K. Mori and H. Yamashita, *Angew. Chem., Int. Ed.*, 2014, 53, 2910–2914.
- 45 P. Liu, Y. Yang and M. G. White, *Surf. Sci. Rep.*, 2013, **68**, 233–272.
- 46 S. Kattel, P. Liu and J. G. Chen, *J. Am. Chem. Soc.*, 2017, **139**, 9739–9754.
- 47 J. J. Birtill and P. G. Dickens, *Mater. Res. Bull.*, 1978, **13**, 311–316.
- 48 S. Adams, J. Solid State Chem., 2000, 149, 75-87.
- 49 B. Braïda, S. Adams and E. Canadell, *Chem. Mater.*, 2005, 17, 5957–5969.
- 50 N. A. Chernova, M. Roppolo, A. C. Dillon and M. S. Whittingham, *J. Mater. Chem.*, 2009, **19**, 2526–2552.
- 51 X. W. Lou and H. C. Zeng, Chem. Mater., 2002, 14, 4781–4789.
- 52 P. A. Sermon and G. C. Bond, Catal. Rev., 1973, 8, 211-239.
- 53 S. Masuda, K. Shun, K. Mori, Y. Kuwahara and H. Yamashita, *Chem. Sci.*, 2020, **11**, 4194–4203.
- 54 P. A. Sermon and G. C. Bond, *J. Chem. Soc., Faraday Trans.* 1, 1976, 72, 730–744.

55 R. Erre, H. van Damme and J. J. Fripiat, Surf. Sci., 1983, 127,

Edge Article

- 56 R. Erre, H. van Damme and J. J. Fripiat, *Surf. Sci.*, 1983, **127**, 69–82.
- 57 J. G. Kim and J. R. Regalbuto, *J. Catal.*, 1993, **139**, 175–190.
- 58 Y.-H. Lei and Z.-X. Chen, *J. Phys. Chem. C*, 2012, **116**, 25757–25764.
- 59 J. Z. Ou, J. L. Campbell, D. Yao, W. Wlodarski and K. Kalantar-zadeh, *J. Phys. Chem. C*, 2011, **115**, 10757–10763.
- 60 M. Vasilopoulou, A. M. Douvas, D. G. Georgiadou, L. C. Palilis, S. Kennou, L. Sygellou, A. Soultati, I. Kostis, G. Papadimitropoulos, D. Davazoglou and P. Argitis, *J. Am. Chem. Soc.*, 2012, 134, 16178–16187.
- 61 H. Cheng, M. Wen, X. Ma, Y. Kuwahara, K. Mori, Y. Dai, B. Huang and H. Yamashita, *J. Am. Chem. Soc.*, 2016, 138, 9316–9324.
- 62 H. Cheng, X. Qian, Y. Kuwahara, K. Mori and H. Yamashita, *Adv. Mater.*, 2015, **27**, 4616–4621.
- 63 H. S. Kim, J. B. Cook, H. Lin, J. S. Ko, S. H. Tolbert, V. Ozolins and B. Dunn, *Nat. Mater.*, 2017, **16**, 454–460.
- 64 A. Borgschulte, O. Sambalova, R. Delmelle, S. Jenatsch, R. Hany and F. Nuesch, *Sci. Rep.*, 2017, 7, 40761.
- 65 J. J. Birtill and P. G. Dickens, *J. Solid State Chem.*, 1979, 29, 367–372.
- 66 N. Sotani, K. Eda, M. Sadamitu and S. Takagi, *Bull. Chem. Soc. Ipn.*, 1989, 62, 903–907.
- 67 S. Chen, H. Wang, Z. Kang, S. Jin, X. Zhang, X. Zheng, Z. Qi, J. Zhu, B. Pan and Y. Xie, *Nat. Commun.*, 2019, 10, 788.

- 68 X. Yang, S. Wang, N. Yang, W. Zhou, P. Wang, K. Jiang, S. Li, H. Song, X. Ding, H. Chen and J. Ye, *Appl. Catal.*, B, 2019, 259, 118088.
- 69 R. Radhakrishnan, C. Reed, S. T. Oyama, M. Seman, J. N. Kondo, K. Domen, Y. Ohminami and K. Asakura, *J. Phys. Chem. B*, 2001, **105**, 8519–8530.
- 70 Y. N. Zhou, J. Ma, E. Hu, X. Yu, L. Gu, K. W. Nam, L. Chen, Z. Wang and X. Q. Yang, *Nat. Commun.*, 2014, 5, 5381.
- 71 P. Mars and D. W. van Krevelen, Chem. Eng. Sci., 1954, 3, 41-59.
- 72 A. V. Mironenko and D. G. Vlachos, *J. Am. Chem. Soc.*, 2016, **138**, 8104–8113.
- 73 S. Gaur, H. Wu, G. G. Stanley, K. More, C. S. S. R. Kumar and J. J. Spivey, *Catal. Today*, 2013, 208, 72–81.
- 74 Y. F. Li, W. Lu, K. Chen, P. Duchesne, A. Jelle, M. Xia, T. E. Wood, U. Ulmer and G. A. Ozin, *J. Am. Chem. Soc.*, 2019, 141, 14991–14996.
- 75 Y. F. Li, N. Soheilnia, M. Greiner, U. Ulmer, T. Wood, A. A. Jelle, Y. Dong, A. P. Yin Wong, J. Jia and G. A. Ozin, *ACS Appl. Mater. Interfaces*, 2019, **11**, 5610–5615.
- 76 S. Bai, Q. Shao, P. Wang, Q. Dai, X. Wang and X. Huang, J. Am. Chem. Soc., 2017, 139, 6827–6830.
- 77 A. Lubezky, L. Chechelnitsky and M. Folman, *J. Chem. Soc., Faraday Trans.*, 1996, **92**, 2269–2274.
- 78 H. Bahruji, M. Bowker, G. Hutchings, N. Dimitratos, P. Wells, E. Gibson, W. Jones, C. Brookes, D. Morgan and G. Lalev, *J. Catal.*, 2016, 343, 133–146.